5-60

PLAN VIEW
SCALE : 1"=100'

SITE LOCATION MAP
SCALE : 1" = 2,000'

PROPERTY SURVEY
NEAR LANDFILL
SCALE : 1" = 500' APPROX.

SITE CLOSURE NOTES

1. ALL DEPRESSIONS AND ERODED SURFACES ON THE LANDFILL CAP SHALL BE IMMEDIATELY REGRADED AND SEEDED.
2. EXISTING VEGETATION SHALL BE MAINTAINED, AREAS OF BARE SOIL SHALL BE SEEDED.

LUDOWICI-CELADON, INC. (OPERATING AS ROOF TILE ACQUISITION CORP.) LANDFILL

P.O. BOX 69
NEW LEXINGTON, OHIO
43764

OPERATED 1960 (EST) TO 1989

ACCEPTED SCRAP CLAY MATERIAL, OFFICE WASTE AND CAFETERIA WASTE PRODUCTS.

TOTAL AREA OF FILL (APPROX)	5.88 AC
DEPTH OF FILL (AVERAGE)	15 FT.
VOLUME OF REFUSE	142,350 C.Y.

Certificate Date Entered.
Approval for transfer to be
to the Auditor's Office.
10-30-1990 RCH
Perry County Engineer's Ofs.

FILED FOR RECORD THIS 30th DAY OF October, 1990 AT 9:25 A.M
FEE N/D FILE NO. _____ RECORDER, PERRY COUNTY, OHIO
RECORDED THIS 30TH DAY OF October, 1990 PLAT 5 PAGE 60
SLOT 252-A
See Affidavit #3169
Recorded in O.R. Vol 64
Pg 937
Barbara Reef - Recorder
~~DEPUTY~~ RECORDER, PERRY COUNTY, OHIO

DESIGNED BY: RSZ	JOB NUMBER: 2292.1	LUDOWICI-CELADON, INC (OPERATING AS ROOF TILE ACQUISITION CORP.)	LANDFILL CLOSURE
DRAWN BY: VCS	SCALE: AS NOTED		
CHECKED BY: PEB	DATE: OCTOBER 1990		
APPROVED BY: PEB	REVISED:		

PLAN VIEW

R.D. Zande & Associates, Limited

PLOT PLAN VIEW LANDFILL CLOSURE - 172(0.86)PF: LNDFIL 42 07-Sep-90 02:59 PM / 2292-8003